


duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer capacity, see detail 1d.

shorter than the normal (10-yr) load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For Minimum 1-3/4" concentrated vertical load transfer capacity, see detail 1d. bearing required

1-1/8" Rim Board Plus 2,600 4,000 detail 1 Provide lateral bracing per detail 1a, 1b, or 1c

1/8" to 1/4" gap between top flange and filler block

	Joist Series		Simple	spans		Multiple spans						
Joist Depth			On cente	r spacing		On center spacing						
	Jenes	12"	16"	19.2	24"	12"	16"	19.2"	24"			
	NI-20	16'-7"	15'-3"	14'-5"	13'-6"	18'-1"	16'-7"	15'-8"	14'-2"			
	NI-40x	18'-8"	17'-0"	16'-1"	15'-0"	20'-4"	18'-5"	16'-10"	15'-0"			
9-1/2"	NI-60	18'-11"	17'-4"	16'-4"	15'-3"	20'-8"	18'-10"	17'-9"	16'-7"			
	NI-70	20'-6"	18'-9"	17'-8"	16'-5"	22'-4"	20'-4"	19'-2"	17'-10			
	NI-80	20'-11"	19'-1"	18'-0"	16'-9"	22'-9"	20'-9"	19'-6"	18'-2"			
	NI-20	19'-11"	18'-3"	17'-3"	16'-1"	21'-8"	19'-10"	17'-9"	16'-2"			
	NI-40x	22'-2"	20'-3"	19'-2"	17'-2"	24'-2"	21'-0"	19'-2"	17'-1"			
11-7/8"	NI-60	22'-8"	20'-8"	19'-6"	18'-2"	24'-8"	22'-6"	21'-2"	19'-8"			
	NI-70	24'-5"	22'-3"	21'-0"	19'-7"	26'-8"	24'-3"	22'-10"	21'-3"			
	NI-80	24'-11"	22'-8"	21'-4"	19'-11"	27'-1"	24'-8"	23'-3"	21'-7"			
	NI-90	25'-7"	23'-3"	21'-11"	20'-5"	27'-10"	25'-4"	23'-10"	22'-2"			
	NI-90x	25'-9"	23'-6"	22'-1"	20'-7"	28'-1"	25'-6"	24'-1"	22'-4"			
	NI-40x	25'-2"	22'-11"	21'-2"	18'-11"	26'-8"	23'-1"	21'-1"	18'-10			
	NI-60	25'-9"	23'-6"	22'-2"	20'-8"	28'-0"	25'-7"	24'-1"	21'-7"			
14"	NI-70	27'-8"	25'-3"	23'-9"	22'-2"	30'-2"	27'-6"	25'-10"	24'-1"			
14"	NI-80	28'-3"	25'-9"	24'-3"	22'-7"	30'-10"	28'-0"	26'-5"	24'-6"			
	NI-90	29'-0"	26'-5"	24'-10"	23'-1"	31'-7"	28'-9"	27'-1"	25'-2"			
	NI-90x	29'-4"	26'-9"	25'-2"	23'-5"	32'-0"	29'-1"	27'-5"	25'-5"			
16"	NI-60	28'-6"	26'-0"	24'-7"	22'-10"	31'-1"	28'-4"	26'-0"	23'-3"			
	NI-70	30'-8"	27'-11"	26'-4"	24'-6"	33'-5"	30'-5"	27'-3"	26'-7"			
	NI-80	31'-4"	28'-6"	26'-10"	25'-0"	34'-2"	31'-1"	29'-3"	27'-2"			
	NI-90	32'-1"	29'-2"	27'-6"	25'-7"	35'-0"	31'-10"	29'-11"	27'-10			
	NIL OO.			07111	0/1 01		201.21	201 51	001.01			



to one side of the double joist using this detail is 620 lbf/ft. Verify double I-joist capacity.

strap applied to underside of joist at blocking


ne or 1/2 inch minimum gypsum ceiling

attached to underside of joists

required in the first joist space (or first and second joist

code requirements for spacing of the blocking.

space) next to the starter joist. Where required, see local



RULES FOR CUTTING HOLES AND DUCT CHASE OPENINGS:

. The distance between the inside edge of the support and the centerline of any hole or duct chase opening shall be in compliance with the requirements of Table 1 or 2,

2. I-joist top and bottom flanges must NEVER be cut, notched, or otherwise modified.

3. Whenever possible, field-cut holes should be centered on the middle of the web. 4. The maximum size hole or the maximum depth of a duct chase opening that can be cut into an I-joist web shall equal the clear distance between the flanges of the I-joist minus 1/4 inch. A minimum of 1/8 inch should always be maintained between the top or bottom of the hole or opening and the adjacent I-joist flange.

. The sides of square holes or longest sides of rectangular holes should not exceed 3/4 of the diameter of the maximum round hole permitted at that location

Where more than one hole is necessary, the distance between adjacent hole edges shall exceed twice the diameter of the largest round hole or twice the size of the largest square hole (or twice the length of the longest side of the longest rectangular hole or duct chase opening) and each hole and duct chase opening shall be sized and located in compliance with the requirements of Tables 1 and 2, respectively. 7. A knockout is **not** considered a hole, may be utilized anywhere it occurs, and may be ignored for purposes of calculating minimum distances between holes and/or

8. Holes measuring 1-1/2 inches or smaller shall be permitted anywhere in a cantilevered section of a joist. Holes of greater size may be permitted subject to verification. 9. A 1-1/2 inch hole or smaller can be placed anywhere in the web provided that it

10. All holes and duct chase openings shall be cut in a workman-like manner in accordance with the restrictions listed above and as illustrated in Figure 7.

12. A group of round holes at approximately the same location shall be permitted if they eet the requirements for a single round hole circumscribed around them

OCATION OF CIRCULAR HOLES IN JOIST WERS Simple or Multiple Span for Dead Loads up to 10 psf and Live Loads up to 40psf

Joist	Joist	Minimum distance from inside face of any support to center of hole (ft-in.)											Span				
Depth	Series	Round hole diameter (in.)												adjustment			
Depin	561165	2	3	4	5	6	6-1/4	7	8	8-5/8	9	10	10-3/4	11	12	12-3/4	Factor
	NI-20	0'-7"	1'-4"	2'-8"	4'-0"	5'-5"	5'-9"										13'-6"
	NI-40x	0'-7"	1'-4"	2'-8"	4'-2"	5'-8"	6'-2"										15'-0"
9-1/2"	NI-60	1'-0"	2'-4"	3'-9"	5'-3"	6'-10"	7'-3"										15'-3"
	NI-70	1'-10"	3'-3"	4'-8"	6'-2"	7'-9"	8'-3"										16'-5"
	NI-80	2'-0"	3'-5"	4'-10"	6'-4"	8'-0"	8'-5"										16'-9"
	NI-20	0'-7"	0'-8"	0'-10"	2'-0"	3'-4"	3'-9"	4'-9"	6'-3"	7'-5"							16'-1"
11-7/8" NI	NI-40x	0'-7"	0'-8"	1'-0"	2'-4"	3'-8"	4'-0"	5'-2"	6'-8"	8'-0"							17'-2"
	NI-60	0'-7"	1'-4"	2'-8"	4'-0"	5'-5"	5'-10"	7'-0"	8'-8"	9'-9"							18'-2"
	NI-70	1'-2"	2'-5"	3'-9"	5'-2"	6'-8"	7'-0"	8'-2"	9'-10"	11'-0"							19'-7"
	NI-80	1'-4"	2'-8"	4'-0"	5'-4"	6'-10"	7'-3"	8'-5"	10'-2"	11'-3"							19'-11"
	NI-90	0'-7"	0'-8"	1'-3"	2'-11"	4'-8"	5'-2"	6'-6"	8'-6"	9'-11"							20'-5"
	NI-90x	0'-7"	0'-8"	0'-8"	2'-3"	4'-2"	4'-6"	6'-0"									20'-7"
	NI-40x	0'-7"	0'-8"	0'-8"	0'-9"	2'-0"	2'-4"	3'-4"	4'-9"	5'-9"	6'-3"	8'-0"	9'-9"				18'-11"
	NI-60	0'-7"	0'-8"	1'-3"	2'-6"	4'-0"	4'-3"	5'-3"	6'-9"	7'-9"	8'-3"	10'-2"	11'-10"				20'-8"
14"	NI-70	0'-7"	1'-8"	3'-0"	4'-3"	5'-8"	6'-0"	7'-0"	8'-6"	9'-6"	10'-2"	12'-0"	13'-4"				22'-2"
	NI-80	0'-8"	1'-10"	3'-2"	4'-6"	6'-0"	6'-3"	7'-4"	8'-10"	9'-10"	10'-6"	12'-3"	13'-8"				22'-7"
	NI-90	0'-7"	0'-8"	0'-9"	2'-3"	3'-10"	4'-3"	5'-6"	7'-3"	8'-5"	9'-2"	11'-2"	12'-9"				23'-1"
	NI-90x	0'-7"	0'-8"	0'-8"	1'-10"	3'-6"	4'-0"	5'-3"	7'-0"	8'-3"	9'-0"						23'-5"
16"	NI-60	0'-7"	0'-8"	0'-8"	1'-2"	2'-5"	2'-9"	3'-9"	5'-0"	6'-0"	6'-6"	8'-0"	9-2"	9'-8"	11'-9"	13'-9"	22'-10"
	NI-70	0'-7"	0'-9"	2'-0"	3'-3"	4'-8"	5'-0"	6'-0"	7'-5"	8'-4"	9'-0"	10'-5"	11'-9"	12'-2"	14'-0"	15'-5"	24'-6"
	NI-80	0'-7"	1'-2"	2'-4"	3'-8"	5'-0"	5'-4"	6'-4"	7'-10"	8'-9"	9'-4"	11'-0"	12'-2"	12'-6"	14'-4"	16'-0"	25'-0"
	NI-90	0'-7"	0'-8"	0'-8"	1'-6"	3'-0"	3'-5"	4'-6"	6'-3"	7'-3"	7'-10"	9'-8"	11'-0"	11'-6"	13'-6"	15'-3"	25'-7"
	NI-90x	0'-7"	0'-8"	0'-8"	1'-10"	3'-4"	3'-9"	5'-0"	6'-6"	7'-6"	8'-3"	10'-0"	11'-5"	11'-10"			26'-0"

Above table may be used for I-joist spacing of 24 inches on center or less. Hole location distance is measured from inside face of supports to center of hole. 3. Distances in this chart are based on uniformly loaded joists.

OPTIONAL

The above table is based on the I-joists used at their maximum span. If the I-joists are placed at less than their full allowable span (see Allowable Floor Spans), the minimum distance from the centerline of the hole to the face of any support (D) as given above may be reduced as follows: $D_{reduced} = \frac{L_{actual}}{SAF} \times D$


D_{reduced} Where:

Lactual

Distance from the inside face of any support to center of hole, reduced for less-than-maximum span applications (ft). The reduced distance shall not be less than 6 inches from the face of the support to edge of the hole. The actual measured span distance between the inside faces of supports (ft).

= Span Adjustment Factor given in this table. = The minimum distance from the inside face of any support to center of hole from this table.

If $\frac{L_{actual}}{SAE}$ is greater than 1, use 1 in the above calculation for $\frac{L_{actual}}{SAE}$



for the contractor's convenience to instal electrical or small plumbing lines. They are 1-1/2 inches in diameter, and are spaced 15 inches on center along the length of the I-joist. Where possible, it is preferable to use knockouts instead of field-cut holes.

Knockouts are prescored holes provided



For rectangular holes, avoid over-cutting the corners, as this can cause unnecessary stress concentrations. Slightly rounding the corners is recommended. Starting the rectangular hole by drilling a 1-incl diameter hole in each of the four corners and then making the cuts between the holes is another good method to minimize damage to the I-joist.

TABLE 2 DUCT CH/	ASE OPENI	NG SIZE	S AND L	OCATIO	NS — Siı	mple Spo	an Only			
	Joist	-		ce from ir		<u> </u>		o center o	f opening	g (ft-in.)
Joist Depth					Duct ch	nase leng	yth (in.)			
Depin	Series	8	10	12	14	16	18	20	22	24
	NI-20	4'-2"	4'-7"	5'-0"	5'-5"	5'-10"	6'-2"	6'-8"	7'-1"	7'-6"
9-1/2"	NI-40x NI-60	5'-2" 5'-3"	5'-7" 5'-8"	6'-0" 6'-0"	6'-4" 6'-6"	6'-8" 7'-0"	7'-2" 7'-3"	7'-7" 7'-9"	8'-1" 8'-3"	8'-8" 8'-10"
/-1/2	NI-70	5'-1"	5'-4"	5'-9"	6'-1"	6'-6"	7-1"	7'-4"	8'-0"	8'-3"
	NI-80	5'-2"	5'-7"	6'-0"	6'-4"	6'-8"	7'-2"	7'-7"	8'-1"	8'-6"
	NI-20	5'-9"	6'-2"	6'-8"	7'-1"	7'-5"	8'-0"	8'-4"	9'-0"	9'-5"
	NI-40x NI-60	6'-7" 7'-1"	7'-1" 7'-7"	7'-6" 8'-0"	8'-1" 8'-4"	8'-6" 8'-10"	9'-1" 9'-3"	9'-7" 9'-9"	10'-2" 12'-4"	10'-9" 11'-2"
11-7/8"	NI-70	7'-0"	7-7 7'-3"	8-0 7'-9"	8'-1"	8'-6"	9-3 9'-1"	9-9 9'-6"	12-4 10'-0"	10'-5"
11-770	NI-80	7'-1"	7'-5"	8'-0"	8'-4"	8'-10"	9'-2"	9'-8"	10'-2"	10'-8"
	NI-90	4'-3"	4'-10"	5'-4"	5'-11"	6'-6"	7'-1"	7'-8"	8'-3"	8'-11"
	NI-90x	7'-6"	8'-1"	8'-4"	8'-9"	9'-2"	9'-8"	10'-1"	10'-7"	11'-2"
	NI-40x	7'-9"	8'-3"	8'-10"	9'-5"	10'-1"	10'-7"	11'-3"	12'-1"	12'-9"
	NI-60 NI-70	8'-8" 8'-6"	9'-2" 9'-1"	9'-6" 9'-4"	10'-1" 9'-10"	10'-6" 10'-2"	11'-1" 10'-8"	11'-7" 11'-2"	12'-4" 11'-8"	13'-2" 12'-4"
14"	NI-80	8'-9"	9'-2"	9'-4 9'-8"	10'-1"	10-2	11'-1"	11'-6"	12'-1"	12-4
	NI-90	5'-10"	6'-5"	7'-0"	7'-6"	8'-2"	8'-9"	9'-4"	9-11"	10'-8"
	NI-90x	9'-3"	9'-8"	10'-2"	10'-7"	11'-1"	11'-6"	12'-1"	12'-8"	13'-3"
	NI-60	10'-1"	10'-7"	11'-0"	11'-6"	12'-1"	12'-7"	13'-4"	14'-2"	15'-0"
16"	NI-70 NI-80	10'-1"	10'-4"	10'-10"	11'-4"	11'-8"	12'-2"	12'-9"	13'-4"	14'-0"
10	NI-80	10'-3" 7'-4"	10'-9" 7'-11"	11'-2" 8'-6"	11'-7" 9'-1"	12'-1" 9'-8"	12'-7" 10'-3"	13'-2" 13'-0"	13'-9" 11'-7"	14'-6" 12'-3"
	NI-90x	111-1"	11'-4"	11'-10"	12'-3"	12'-8"	13'-3"	14'-0"	14'-7"	12-3

I. Above table may be used for I-joist spacing of 24 inches on center or less 2. Duct chase opening location distance is measured from inside face of supports to center of opening

The above table is based on simple-span joists only. For other applications, contact your local distributor.
Distances are based on uniformly loaded floor joists that meet the span requirements for a design live load of 40 psf and dead load of 10 psf, and a live load deflection limit of L/480. For other applications, contact your local distributor.

INSTALLING THE GLUED FLOOR SYSTEM

1. Wipe any mud, dirt, water, or ice from I-joist flanges before gluing.

2. Snap a chalk line across the I-joists four feet in from the wall for panel edge alignment and as a

3. Spread only enough glue to lay one or two panels at a time, or follow specific recommendations from

4. Lay the first panel with tongue side to the wall, and nail in place. This protects the tongue of the next panel from damage when tapped into place with a block and sledgehamme 5. Apply a continuous line of glue (about 1/4-inch diameter) to the top flange of a single I-joist. Apply

glue in a winding pattern on wide areas, such as with double I-joists.

6. Apply two lines of glue on I-joists where panel ends butt to assure proper gluing of each end.

7. After the first row of panels is in place, spread glue in the groove of one or two panels at a time before laying the next row. Glue line may be continuous or spaced, but avoid squeeze-out by applying

8. Tap the second row of panels into place, using a block to protect groove edges.

9. Stagger end joints in each succeeding row of panels. A 1/8-inch space between all end joints and 1/8-inch at all edges, including T&G edges, is recommended. (Use a spacer tool or an 8d common nail to assure accurate and consistent spacing.)

10. Complete all nailing of each panel before glue sets. Check the manufacturer's recommendations for cure time. (Warm weather accelerates glue setting.) Use 6d ring- or screw-shank nails for panels 3/4-inch thick or less, and 8d ring- or screw-shank nails for thicker panels. Space nails per the table below. Closer nail spacing may be required by some codes, or for diaphraam construction. The finished deck can be walked on right away and will carry construction loads without damage to the

APA RATED STURD-I-FLOOR FASTENER SCHEDULES FOR NI's(1)

inel		Fastening: Glued-Nailed ⁽³⁾ Maximum Spacing (in.)						
ness ⁽²⁾	Nail Size							
n.)	and Type	Supported Panel Edges	Intermediate Supports					
₃₂ (5)	6d ring-or screw-shank ⁽⁴⁾	12	12					
₃₂ (5)	6d ring-or screw-shank ⁽⁴⁾	12	12					
32, 3/4	6d ring-or screw-shank ⁽⁴⁾ 8d ring-or screw-shank ⁽⁴⁾	12 6	12 12					

(1) Special conditions may impose heavy traffic and concentrated loads that require construction in

Panels in a given thickness may be manufactured in more than one allowable span. Panels with an allowable span greater than the actual joist spacing may be substituted for panels of the same thickness with an allowable span matching the actual joist spacing. For example, 19/32-inch-thick Sturd-I-Floor 20 oc may be substituted for 19/32-inch-thick Sturd-I-Floor 16 oc over joists 16 inches

(3) Use only adhesives conforming to APA Specification AFG-01, or ASTM D3498 applied in accordance with the manufacturer's recommendations. If OSB panels with sealed surfaces and edges are to be used, use only solvent-based glues; check with panel manufacturer.

(4) 8d common nails may be substituted if ring- or screw-shank nails are not available.

(5) Recommended minimum thickness for use with I-joists.

Floor sheathing must be field glued to the I-joist flanges in order to achieve the allowable spans shown in this document. If sheathing is nailed only, reduce I-joist spans in the

